

MIDDLETON ASSOCIATES INCORPORATED
1702 W. COLLEGE AVE., SUITE E
NORMAL, IL 61761-2793
309/452-1271 FAX 309/454-8049

August 31, 2017

ADDENDUM NUMBER 1
TO THE DRAWINGS AND SPECIFICATIONS

PROJECT: 2017 Addition to Lincoln Elementary School

FOR: Macomb CUSD #185
323 W. Washington Street
Macomb, IL 61455

A/E PROJECT NO: 2200 0216

ISSUE DATE: August 31, 2017

BID OPENING: Tuesday, September 12, 2017 – 3:15 p.m. THIS ADDENDUM DOES NOT CHANGE THE BID DATE.

Upon receipt of this ADDENDUM, insert same into the documents, which were issued to you. Hereafter, said ADDENDUM shall be as much a part of the said documents as though originally set forth therein.

1. TO THE SPECIFICATIONS, Section 07 4100 Metal Roof and Soffit Panels:

Clarification, there are no metal roof or soffits on this project. This specification applies to the exterior metal wall panels on Alternate #1, Penthouse.

To 07 4100 / 2.1.C.1.b Metal Wall Systems add: Pac Clad Peterson Aluminum 7.2 Panel as equal.

2. TO THE SPECIFICATIONS, Section 08 1140 Aluminum Door & Frames:

08 1140 / 2.1.6 add Manko Window Systems, 800 Hayes Drive, Manhattan KS 66502 as equal. Ph. 785-776-9643 Fax 785-776-9644. 08-1140 / 2.1.6.4 add Manko 170 FRP as equal.

08 1140/3.3 Schedule of openings ALTERNATE BID. These are insulated hollow metal doors 30 and 31 on the door schedule.

3. TO THE SPECIFICATIONS, Section 08 1400 Flush Wood Doors:

08 1400/2.1.A.1.e add Oshkosh Wood Doors

ADDENDUM NUMBER 1
TO THE DRAWINGS AND SPECIFICATIONS
PROJECT: 2017 Addition to Lincoln Elementary School

4. TO THE SPECIFICATIONS, Section 08 7100 Door Hardware:

The following hardware equivalent for bidding assume nominal compliance with specifications and does not allow any variance to grade, quality, or function.

08 7100/2.1.F.1.f Closers, add Stanely, and Dorma
08 7100/2.1.G. Door Stops, Nominal match specified, add Trimco
08 7100/2.1.H. Push-Pull, Nominal match specified, add Trimco
08 7100/2.1.I. Kick Plates, Nominal match specified, add Trimco
08 7100/2.1.L. Louvers, Nominal match specified, add NGP L-700 RX National Guard Products
08 7100/3.7 Set D, Add 24" wide 12" Louver

5. TO THE SPECIFICATIONS, Section 09 6713 Padded Urethane Floor:

09 6715 2.1.A.4 add Robbins Strata-Sport[®] Plus 7mm pad two part urethane floor padded floor system as approved equal.

Add Champion Monoflex 7 + 2 by Champion L.L.C. as approved equal.

6. TO THE SPECIFICATIONS, Section 11 6600 Athletic Equipment:

Add to 2.1 Manufacturers

D. ADP Lemco 5970 W. Dannon Way, West Jordan, UT 84081, Phone 801/280 4000, FAX 801/280-4080, e-mail: dhall@adplemco.com.

E. ACI, Arizona Courtlines, Inc., 8742 N. 78th Avenue, Peoria, AZ Phone: 623/939-8126, Fax 623/939-2526, e-mail: alesia@arizonacourtlines.com

7. TO THE SPECIFICATIONS, Section 23 0713, Section 23 3100 and drawing's sheet M4.1 Duct Insulation Schedule:

Exterior Duct work may be ThermaDuct OD R-12, ThermaDuct LLC 26610 Eckel Road, Perrysburg, Ohio 43551, Phone: 855/566-5382

8. TO THE SPECIFICATIONS, Section 23 0913, Instrumentation and Control Devices for HVAC:

Provide Building Automation System (BAS) for all new equipment in the new addition and the new equipment for the cafeteria. All equipment, HVAC, thermostats, fans, ERUs, Geothermal Units and pumps as may occur shall include control cards to allow BAS to monitor and control operation.

Control systems to be included in the Base Bid to be as designed by Environmental Control Solutions, Inc. (ECSI) Peoria, IL. Contact John Evans 309/683-5252, jevans@ecsi-alc.com.

ADDENDUM NUMBER 1
TO THE DRAWINGS AND SPECIFICATIONS
PROJECT: 2017 Addition to Lincoln Elementary School

9. TO THE DRAWINGS, Sheet A-2.0 West Elevation:

Not shown on the exterior elevation of the existing upper gym wall, use (2) louvers being removed under note 11 on sheet MO.1 as modified in this addendum #1 to be removed. Infill louver opening with CMU and face brick. Lintel may remain in place.

10. TO THE DRAWINGS, Sheets A-3.0, A-3.1, A-3.2, A-5.0, A-5.1 Clarification:

Roof insulation to be per specification two (2) layers 2" iso board with ½" cap layer of HD iso board.

Notes on sheets A-3.1 and A-3.2 in particular fail to denote two (2) layers of 2" board.

Notes on sheets A-5.0 have 1" + 3" + ½" in some cases, intent is two (2) layers 2" plus ½" HD cap board.

11. TO THE DRAWINGS, Sheet A-5.0 and any other location:

delete reference to vapor barrier in details 1/A5.0, 2/A5.0, 4/A5.0, 5/A5.0, 7/A5.0, 8/A5.0 and any other location in details or section.

12. TO THE DRAWINGS SHEET A-6.0, Door Schedule:

Delete A4 and A5. These are to be insulated, galvanized hollow metal doors 30 and 31 in the schedule.

13. TO THE DRAWINGS, Sheet E-5.0 Technology and Security Plan:

Add CAT 6 wiring for Wireless Access Point, (WAP) six (6) locations, ceiling or underside of deck. Where no drop ceiling, provide conduit, provide jack and 20' coil of wire at Ethernet Patch Panel. Locations: Reading Center Room 035, Cafeteria room 046, Teacher Work Room 052, Gymnasium Room 55 – two (2) required, and Corridor C-5 south entry.

Add nine (9) note (3) modular double jacks. Room 035 – north wall, Room 38 – north wall, Room 52 – south wall, Room 54 – east wall, Room 58 west wall north of door, Room 48 west wall near southwest corner, Room 59 – west wall near southwest corner.

14. TO THE DRAWINGS, Sheet M-0.1 Demo HVAC Plan:

Equipment associated with note 11, completely remove the abandoned equipment, associated piping in the adjacent space and the pneumatic control board and piping tree wall mounted below.

Work includes removing thru wall louvers, patching openings in masonry, patching walls in finished areas touching up finishes.

END ADDENDUM NO. 1