

MIDDLETON ASSOCIATES INCORPORATED  
1702 W. COLLEGE AVE., SUITE E  
NORMAL, IL 61761-2793  
309/452-1271 FAX 309/454-8049

September 7, 2017

ADDENDUM NUMBER 2  
TO THE DRAWINGS AND SPECIFICATIONS

PROJECT: 2017 Addition to Lincoln Elementary School

FOR: Macomb CUSD #185  
323 W. Washington Street  
Macomb, IL 61455

A/E PROJECT NO: 2200 0216

ISSUE DATE: September 7, 2017

BID OPENING: **THIS ADDENDUM DOES NOT CHANGE THE BID DATE,  
September 12, 2:00 p.m.**

Upon receipt of this ADDENDUM, insert same into the documents, which were issued to you. Hereafter, said ADDENDUM shall be as much a part of the said documents as though originally set forth therein.

15. TO ADDENDUM #1. Delete the information reminder on Bid date and time. **Bid remains due on Tuesday, September 12, at 2:00 p.m. as set forth in the document and legal advertisement.**

16. TO THE SPECIFICATIONS, Section 07 4100 Metal Roof and Soffit Panels.

Reminder there are no Metal Roof and Soffits, this section includes metal wall system, see Addendum #1 item 1.

Add 2.1 F

Liner panel (Alternate #1) to be standard 26 gauge galvanized or aluminized liner, white factory finish, white screws, such as McElroy 5V or MBCI 5V Crimp or such generically similar product by any reputable manufacturer.

17. TO THE SPECIFICATIONS, Section 08 3313 Coiling Doors, Clarification – there is some concern that some manufacturer's rated assemblies cannot be face in mounted. Unit may be jamb mount, simply raise the masonry head to accommodate.

There is also concern that the existing wall may be 13" and some manufacturers are only fire equivalent tested to 12" thick wall. Either adjust the jamb to 12" or provide letter certifying rated construction but wall to thick to receive label.

ADDENDUM NUMBER 2  
TO THE DRAWINGS AND SPECIFICATIONS  
PROJECT: 2017 Addition to Lincoln Elementary School

18. TO THE SPECIFICATIONS, Section 09 6713 Padded Urethane Floor:  
Clarification, all systems, wear surface 3mm.

09 6715 2.1.A.4 add Dynamic Sports Inc., Dynaforce Floor System 7mm pad two part urethane floor. Floor system as approve equal.

Add Action Floor Systems L.L.C., Herculon RH 7+3 7 mm pad two part urethane floor.

Disregard the game line description on Sheet A1.1. and follow the description on 09 6713 3.2.E.3.

19. TO THE SPECIFICATIONS, Section 23 0716 Insulation:

Clarification: All equipment connected to the geothermal piping system is to be insulated including:

- Pump bodies
- Expansion tank
- Air separator
- Chemical feeder
- Valves

20. TO THE SPECIFICATIONS, Section 23 7413 Part 2/2.01, add:

E. Daikin Company [www.northamerica-daikin.com](http://www.northamerica-daikin.com)

21. TO THE DRAWINGS, Sheet A-6.0, Door Schedule:

Opening Mark 12, Frame Style, delete HM-4 insert HM-6

22. TO THE MECHANICAL SUBCONTRACTED WORK, See Addendum item to remove abandon kitchen hood, Electrical Contractor to remove associated wiring and device back to junction box that is out of way of new work.

23. TO THE ELECTRICAL SUBCONTRACTED WORK, coordinate with Mechanical Work to remove all electrical associated with the old kitchen (Room 48), kitchen hood removal, including lighting and fan. Properly terminate wiring and raceways above ceiling in walls or remove to panel

24. TO THE ELECTRICAL WORK SUBCONTRACTED AND DRAWINGS, Sheet C-1.1 and ME-2:

**Include Ameren Service modification fee of \$18,000**, over / under will adjust by change order.

Electrical Contractor to extend new 4" conduit to existing service pole in alley along South lot line. We will relocate the new transformer and bollards and transformer foundation not over the existing primary. E.C. can then run new conduit for service entrance as needed prior to service modification work.

ADDENDUM NUMBER 2  
TO THE DRAWINGS AND SPECIFICATIONS  
PROJECT: 2017 Addition to Lincoln Elementary School

E.C. subcontractor to coordinate with General Contractor to provide temporary support or build small section of wall for CT and Entrance rain tight then extend conduit to back feed the existing MDP.

This will take considerable cooperation and coordination of various trades to implement and schedule service change over a weekend or when school is not in session.

25. TO THE DRAWINGS, Sheet D1.0, in the existing kitchen, near handwash sink, remove wall mount fire extinguisher, remount as directed in new kitchen.
26. TO THE ELECTRICAL DRAWINGS, Sheet E-3.1, Intercom. Existing intercom is Dukane Model MCS350/64-25-1 with 64 spaces used. An expansion module will be required. This was installed originally by Thompson Electronics in Peoria.
27. TO THE ELECTRICAL DRAWINGS, Sheet E-5.0 gymnasium sound system, note 5. Amplifier will be in SE corner of P.E. Storage Room #56. Work includes conduit and Speaker wire to two locations wired microphone to one location. Microphone and speakers located as described in note 5.

**Electrical Contractor or General Contractor to include \$7,500 allowance** for the actual equipment system, speakers. Wiring and conduit are base bid. Over / under \$7,500 will adjust by change order.

28. TO THE PLUMBING DRAWINGS, Sheet ME-2:

Plumbing Contractor or General Contractor to include an **allowance for Ameren for service charges of \$3,000**. Over / under will be adjusted by change order.

29. TO THE DRAWINGS, Sheet MO.1 Demo HVAC Plan, Room 48, off the old gym.

There is an existing kitchen hood and roof fan to remove. Remove hood, duct work, and fan. Cap curb for weather.

END ADDENDUM NO. 2