

February 28, 2018

MIDDLETON ASSOCIATES INCORPORATED  
1702 W. COLLEGE AVE., SUITE E  
NORMAL, IL 61761-2793  
309/452-1271 FAX 309/4654-8049

ADDENDUM NUMBER 1  
TO THE DRAWINGS AND SPECIFICATIONS

PROJECT: Normal Community West High School Tennis Court Resurface Project 2018

FOR: McLean Co. Unit District No. 5  
1809 W. Hovey Ave.  
Normal, IL 61761

A/E PROJECT NO: 22722216

ISSUE DATE: February 13, 2018

**BID OPENING: Thursday, March 8, 2018 – 2:30 p.m. – THIS ADDENDUM DOES NOT CHANGE THE BID DATE.**

Upon receipt of this ADDENDUM, insert same into the documents, which were issued to you. Hereafter, said ADDENDUM shall be as much a part of the said documents as though originally set forth therein. Acknowledge receipt of this addendum in space provided on Bid Form. FAILURE TO DO SO MAY SUBJECT THE BIDDER TO DISQUALIFICATION.

1. TO THE SPECIFICATIONS: Section 01030 Alternates: Add Alternate #2 and Alternate #3:

- B. Alternate No. 2 -- Provide price to replace the East row of Fence posts and the fence fabric (1 ¾" chain link) along the East side of the courts. This is a length of 357.25'. The posts will be one for one replacement. The fence fabric will be 9'-6" high. The replacement fence on the East side will be natural aluminum (no color).
- C. Alternate No. 3 -- Provide price to replace the fence fabric (1 3/4" chain link) on the North, West and East and the two dividing fences with new black vinyl covered fabric 1 ¾" square. This is using existing posts on the North, West, South and two divider fences between courts.

Note: The Base Bid will be as described on Drawing C-4, note 2, 3 and 4 and as described in Specification Section 116615 paragraph 3.3.I. & O. The Base Bid also includes 576 ft. x 6 ft. wind break fabric as described in Specification Section 116615 paragraph 3.3.L.

- 2. TO THE DRAWINGS: Sheet C-4 Note 6: Delete note 6. The concrete contractor will install concrete form all along East side of the fence posts and pour concrete to the form. The asphalt contractor will finish asphalt to top of the new top of the new concrete.
- 3. TO THE DRAWINGS: Sheet C-4 Detail 1/C-4: The net anchor at the center of each of the six nets will not be anchored in new concrete as shown in this detail. The new center net anchor (six (6) total) will be mounted on a steel pipe anchor supplied and installed by the subcontractor installing the finish surfacing.

END ADDENDUM NO. 1