

MIDDLETON ASSOCIATES INCORPORATED
1702 W. COLLEGE AVE., SUITE E
NORMAL, IL 61761-2793
309/452-1271 FAX 309/454-8049

April 8, 2019

ADDENDUM NUMBER 3
TO THE DRAWINGS AND SPECIFICATIONS

PROJECT: Edison Elementary School 2019 Addition

FOR: Macomb CUSD #185
323 W. Washington Street
Macomb, IL 61455

A/E PROJECT NO: 2275 0217

ISSUE DATE: March 4, 2019

BID OPENING: Wednesday, April 10, 2019 – 2:00 p.m. THIS ADDENDUM DOES NOT CHANGE THE BID DATE.

Upon receipt of this ADDENDUM, insert same into the documents, which were issued to you. Hereafter, said ADDENDUM shall be as much a part of the said documents as though originally set forth therein.

31. TO THE SPECIFICATIONS, Section 07 5323 EPDM Elastomeric Membrane Roofing:

1.1.C.1.a) Clarification, upper classroom roof IBC 120 MPH wind rated is correct. If there any other descriptive notes in spec, disregard, IBC 120 MPH is correct.

1.2.C.1.b) Cafeteria (low roof) IBC 90 MPH is correct.

1.1.C.2.a) Base insulation to be 3 ½" + ½" taper starter. Drawings are correct.

32. TO THE SPECIFICATIONS, Section 10 5113 Corridor Lockers:

3.2.A.2.a) Delete Reference to 292 lockers. Floor plan governs, it appears to be 226 corridor lockers and (2) 60" trash lockers. 15" wide x 12" deep x 30" high double tier.

3.2.A.2.b) Kitchen to be (7) at 60" high x 9" wide x 18" deep. (Width to be manufacturer standard 8" or 9")

3.2.A.2.c) Delete this item

Clarification, all lockers sit on the detailed 4" base and all have sloped tops.

END ADDENDUM 3

Reminder: On A/E website, www.middletonassociates.net, Contractor tab, Edison tab you will find a tab for RFI questions and answers. This is updated periodically and may contain interpretation information of interest to you.

Addendum #3

PAGE 1 OF 1