

January 28, 2021

MIDDLETON ASSOCIATES INCORPORATED  
1702 W. COLLEGE AVE., SUITE E  
NORMAL, IL 61761-2793  
309/452-1271 FAX 309/454-8049

ADDENDUM NUMBER 2  
TO THE DRAWINGS AND SPECIFICATIONS

PROJECT: McLean County Unit District No. 5 Chiddix Junior High School HVAC Renovation

FOR: McLean Co. Unit District No. 5  
1809 W. Hovey Ave.  
Normal, IL 61761

A/E PROJECT NO: 23472320

ISSUE DATE: January 11, 2021

BID OPENING: Thursday, February 5, 2020, 10:00 a.m. prevailing time  
Maintenance Office, 1999 Eagle Road, Normal, IL 61761

THIS ADDENDUM DOES NOT CHANGE THE BID DATE OR BID TIME.

Upon receipt of this ADDENDUM, insert same into the documents, which were issued to you. Hereafter, said ADDENDUM shall be as much a part of the said documents as though originally set forth therein. THIS ADDENDUM DOES NOT CHANGE THE BID DATE.

3. On the east wall of the building, Girls locker room #27, there is an additional exhaust fan to be removed shown on Sheet M1.2 and A1.2, but not on D1.2. Work by General Contractor is shown on A1.2 and work by HVAC Contractor is shown on M1.2. This exhaust fan is also shown on E1.2. The conduit mounted on the concrete ceiling shall be removed back to Storage Room 25 which is approximately 47' of conduit – it is indicated to remain on Sheet E1.2.
4. TO THE SPECIFICATIONS: Specification Section 081008; indicates two (2) new doors in Room 113. The frame is existing. Paint door and frame to match existing. See also Sheet A1.3.
5. TO THE DRAWINGS: Sheet A1.3 and A1.1; Room 200A – This room has two 2x4 light fixtures in the ceiling to be taken down and re-installed. The closet door in this room is the location of the new 18x18" louver to be installed in the wood door to the closet.
6. TO THE DRAWINGS: Sheet D1.6 and Sheet E1.2; At the east end of Corridor 100H and Sheet E1.2, there is a ceiling heating/cooling unit to be removed. See Sheet M1.2 for demolition. See Sheet E1.13 – Electrical will need to be removed. The General Contractor must provide 24 sq. ft. of new grid and panels for the ceiling.

7. TO THE DRAWINGS: Sheet R1.1 and M1.7; On the roof, the large duct will be removed by General Contractor to the north wall of Mechanical Room 001. General Contractor will protect roof from damage. HVAC Contractor will remove the interior continuation of this duct to the Governair unit. The HVAC Contractor will remove three (3) exhaust fans connected by the large duct and remove from roof. General Contractor will provide 60 mil over three runners supporting the three exhaust fans EF-6, EF-7, and EF-8.
8. TO THE DRAWINGS: Sheet R1.1 and M1.6; Gym roof – the four (4) ventilators on the gym roof will be removed by the HVAC contractor; this is noted on the plans. The General Contractor will remove curbs and patch roof with 60 mil EPDM.
9. TO THE DRAWINGS: Sheet M1.9 and A1.2; Room 31 – New heat pump will be located in front of the single window. General Contractor remove lower window panel (same as lower panel in Detail 3/A 1.2). HVAC Contractor to install a 33"x6" louver. General Contractor to infill surround as shown in 3/A1.2. Sill of the window is 38" above floor. No new panels replacing glazing will be required – leave pull down shade in place.
10. TO THE SPECIFICATIONS: Section 23 8128; Paragraph 3.04.A & C: Change Kingsley Junior High School to Chiddix Junior High School.

END ADDENDUM NO. 2