

April 14, 2020

MIDDLETON ASSOCIATES INCORPORATED
1702 W. COLLEGE AVE., SUITE E
NORMAL, IL 61761-2793
309/452-1271 FAX 309/454-8049

ADDENDUM NUMBER 3
TO THE DRAWINGS AND SPECIFICATIONS

PROJECT: McLean County Unit District No. 5 Glenn Elementary School Teacher Workroom
Remodel and Addition

FOR: McLean Co. Unit District No. 5
1809 W. Hovey Ave.
Normal, IL 61761

A/E PROJECT NO: 24422319

ISSUE DATE: March 23, 2020

BID OPENING: Thursday, April 16, 2020, 1:30 p.m. prevailing time
Maintenance Office, 1999 Eagle Road, Normal, IL 61761
Bids can also be submitted electronically as described in Amendment 2,
Item #7

THIS ADDENDUM DOES NOT CHANGE THE BID DATE OR BID TIME.

Upon receipt of this ADDENDUM, insert same into the documents, which were issued to you. Hereafter, said ADDENDUM shall be as much a part of the said documents as though originally set forth therein. THIS ADDENDUM DOES NOT CHANGE THE BID DATE.

12. TO THE DRAWINGS, Sheet A-1 Office Floor Plan: The existing west wall of the new Office Room 120A is a wall with large glazing panels. The Demo Plan on C-1 called for removal of this wall and installation of metal studs and impact resistant gypsum board. This existing wire glazed wall and terrazzo curb will now remain, except the north 3'w x 7'h wire glass panel will need to be removed and a 4" metal stud wall with impact resistant gypsum board will need to be installed on top of the terrazzo curb; putty, taped, sanded, primed, and two (2) coats painted on the 3' x 7' north panel. The remainder of the wall will remain as is – no demolition and no painting.
13. TO THE SPECIFICATIONS, Section 15010; Basic Mechanical Requirements, Paragraph 3.4.A.1.d and TO THE DRAWINGS, Sheet MEP-1 Mechanical Plan: The proposed fresh air intake box, damper, CO2 sensor, and outside grill will be deleted. All other relocated details of the existing BARD Heat Pump remain as noted.

END ADDENDUM NO. 3