

## Macomb High School football field house questions

1. CMU does not show vertical reinforcement or bond beam. Correct only has horizontal joint reinforcement, alternate joints. Anchor bolts at roof will need to be solid embedded. This is similar to the rest of the adjacent structure.

Remember this is a modified design build proposal, so lintels for example aren't shown but will be required.

2. Fire alarm is it addressable and connected to main building. No, this is stand alone, simply extend from the existing FACP in the coach's office.
3. Alternate 3, how do we bid it, just as base bid? Yes, Alternate 3 to insulate and line the interior should be bid to the base bid package, if Alternates 1 and or 2 are taken, then we will simply proportionally adjust by negotiation if we want Alternate #3 also.