

May13, 2022

MIDDLETON ASSOCIATES INCORPORATED
1702 W. COLLEGE AVE., SUITE E
NORMAL, IL 61761-2793
309/452-1271 FAX 309/454-8049

ADDENDUM NUMBER 1
TO THE DRAWINGS AND SPECIFICATIONS

PROJECT: Livingston County Highway Department New Maintenance Building

FOR: Livingston County Highway Department
1705 S. Manlove St.
Pontiac, IL 61764

A/E PROJECT NO: 2575 3521

ISSUE DATE: April 15, 2022

BID OPENING: Thursday, June 2, 2022, 10:00 a.m. prevailing time
1705 S. Manlove St, Pontiac, IL 61764

THIS ADDENDUM DOES NOT CHANGE THE BID DATE OR BID TIME.

Upon receipt of this ADDENDUM, insert same into the documents, which were issued to you. Hereafter, said ADDENDUM shall be as much a part of the said documents as though originally set forth therein. THIS ADDENDUM DOES NOT CHANGE THE BID DATE.

1. TO THE DRAWINGS; Sheet M500, Radiant Tube Heater Schedule: Equal is Superior Radiant AM 115 for MP 30 115 and AM 200 for MP 60 150.
2. TO THE SPECIFICATIONS; Section 00 0110, Table of Contents: Drawing Index: C106, C107, C108, C109, and C110 are not in the set. C201, C202, C203, C204, C205, C301, C302, C303, C304 are in the set. M200 is listed in the index, but not in the set. M400 is in the set, but not listed.
3. TO THE DRAWINGS; Sheet G101, Index of Drawings: M200 is not in the set, M400 is in the set.
4. TO THE SPECIFICATIONS; Section 13 1200, Pre-Engineered Structures:
 - a. 1.5.B.10.a: Importance Factor may be 1.5
 - b. 2.2.A.6: Crimping not required. Foam fill strip may be employed for infiltration seal.
 - c. 1.10.A: Warranty clarification. Provide manufacturers longest warranty if less than those specified, provide a copy with or prior to bidding. Building to be assembled to highest standards but CICP certification not required. Building will not be pressure tested.
5. TO THE DRAWINGS; Sheet A101, A201: There is to be a sectional overhead door #100b in the southeast half deep bay 12' wide x 12' high, include operator as specified for other doors. Configuration similar with insulated vision panels nominal 5' high.
6. TO THE DRAWINGS; Sheet A101, A201: Overhead sectional doors 100c through 100f are 16' wide x 14' high opening.

7. TO THE DRAWINGS; Sheet C101, notes: Underground sixth paragraph, storm sewer pipe materials to be:
 - a. Roof drain lines along building each side to manhole to be PVC SDR 26.
 - b. Remainder of storm drainage may be PVC SDR 26, RCCP, or ND12 dual wall corrugated, smooth liner.

8. TO THE SPECIFICATIONS; Section 05 500, Metal Fabrications:
 - a. 3.2.D.4.e: There are to be four (4) loose bollards to be installed by the Contractor as directed at fuel dispensing area SW area of site.
 - b. 3.2.D.4.f: Provide also four (4) bollards for the overhead door added by addendum.

9. TO THE DRAWINGS; Sheet P200, Fixture Schedule AC-1: Revise to be Quincy QT-10, Model 2103DS12VCB23

END ADDENDUM NO. 1